PROJECT PROFILE

CORONA DEL SOL HIGH SCHOOL











PROJECT DATA

Location - Tempe, AZ

Application - Self-Leveling Overlayment

Architect/Engineer - ADM Group

General Contractor - Norcon Industries, Inc.

Distributor – Construction Sealants and Supply

Demo/Surface Prep – Southwest Surface Blasting, Inc.

Applicator – Flo-Tech Inc

Total Area - 15,000 ft² (1,394 m²)

PRODUCTS FEATURED

INCRETE HIGH PERFORMANCE EPOXY

2-Part Epoxy for Sand-Saturated Surface Substrate

EUCOFLOOR™ SL 160

Cementitious, Self-Leveling Underlayment

LEVEL TOP PC-AGG

Polishable Self-Leveling Overlayment with Natural Aggregate

SCOPE OF PROJECT

Fill all low areas with EucoFloor SL 160 to make a uniform floor, then pour 3/8 in of Level Top PC-Agg over the whole floor and polish to expose the aggregate. The stairs were form and poured and then hand polished.

PROJECT SUMMARY

The Tempe Unified School District wanted to replace the existing tile in the cafeteria with a more modern and lower maintenance cost alternative. The school district was fully aware of the benefits of polished concrete, but once the tile was removed the existing concrete did not provide a canvas that could achieve the desired look. ADM Group worked with Euclid Chemical and the construction team to find a system that could meet the school districts needs. After looking at a few previous installed jobs it was determined that Level Top PC-AGG was the best product for this application. The result is a stunning polished concrete floor that exceeded the school district representatives expectations.

PR88 @ 2020